



2018 SAUSALITO STREETS RESURFACING PROJECT

CITY OF SAUSALITO
MARIN COUNTY, CA



LOCATION MAP
NOT TO SCALE



PROJECT MAP
NOT TO SCALE

SHEET INDEX

SHEET NAME				SHEET NO.
TITLE SHEET				1
GENERAL NOTES, LEGEND AND ABBREVIATIONS				2
CONSTRUCTION DETAILS				3-4
IMPROVEMENT PLAN - SPENCER AVE				5-8
IMPROVEMENT PLAN - CALEDONIA ST				9-12
IMPROVEMENT PLAN - WOLFBACK RIDGE ROAD				13
TRAFFIC CONTROL PLAN				14-15

PROJECT			
STREET	FROM	TO	RESURFACING TYPE
SPENCER AVE	PROSPECT AVE	HIGHWAY 101	ASPHALT SPOT REPAIRS MICROSURFACE
CALEDONIA ST	NAPA ST	JOHNSON ST	ASPHALT SPOT REPAIRS MICROSURFACE
WOLFBACK RIDGE RD	MONTE MAR DR	OVERPASS	CENTERLINE STRIPING

REVISIONS				NO.	DESCRIPTION	BY	DATE	APPROVED



711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415.930.7680 (TEL)
415.930.7979 (FAX)

BKF
ENGINEERS / SURVEYORS / PLANNERS

DRAWN: BS
CHECKED: DBJ
DESIGNED: CL
APPROVED: DBJ

CALIFORNIA

2018 SAUSALITO STREETS
RESURFACING PROJECT

TITLE SHEET

SAUSALITO
MARIN COUNTY

DATE	JULY 2018	SCALE	AS SHOWN
BKF PROJECT NO.	20165272		
CLIENT	CITY OF SAUSALITO		
SHEET NO.	1	OF	15
DRAWING NO.	TS.01		

STATEMENT OF APPROVAL

APPROVAL OF THESE PLANS DOES NOT RELEASE THE CONTRACTOR OF THE RESPONSIBILITY FOR CORRECTIONS OF MISTAKES, ERRORS OR OMISSIONS CONTAINED THEREIN. IF DURING THE COURSE OF CONSTRUCTION OF THE IMPROVEMENTS, PUBLIC INTEREST REQUIRES A MODIFICATION FOR A DEPARTURE FROM SPECIFICATIONS AND DETAILS OF THE CITY OF SAUSALITO OR THESE PLANS, THE PUBLIC WORKS DIRECTOR SHALL HAVE THE AUTHORITY TO REQUIRE SUCH MODIFICATION OR DEPARTURE AND TO SPECIFY SUCH MODIFICATION OR DEPARTURE AND TO SPECIFY THE MANNER IN WHICH THE SAME IS TO BE MADE.

APPROVED FOR THE CITY OF SAUSALITO

BY: JONATHON GOLDMAN, PE CFM
DIRECTOR OF PUBLIC WORKS

DATE

CITY OF SAUSALITO

ANDREW A. DAVIDSON
CITY OF SAUSALITO SENIOR ENGINEER
415.289.4180
ADAVIDSON@SAUSALITO.GOV
420 LITHO STREET
SAUSALITO, CA 94965

ENGINEER

DAYNE JOHNSON
925.940.2208
DJOHNSON@BKF.COM
BKF ENGINEERS
1646 N CALIFORNIA BLVD SUITE 400
WALNUT CREEK, CA 94596



GENERAL PROJECT NOTES

1. THE CONTRACTOR AGREES THAT, IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT LIMITED TO NORMAL WORKING HOURS.
2. ALL EXISTING FEATURES ARE SHOWN IN THEIR APPROXIMATE LOCATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO FIELD VERIFY LOCATIONS, ELEVATIONS, ETC. OF EXISTING FACILITIES AND TO IMMEDIATELY NOTIFY THE ENGINEER IN WRITING OF ANY FIELD CONFLICTS.
3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN ALL PERMITS NECESSARY TO PERFORM THE WORK SHOWN IN THESE PLANS FROM THE APPROPRIATE AGENCIES, PRIOR TO PERFORMING ANY WORK.
 - 3.1. CITY OF SAUSALITO ENCROACHMENT PERMIT
 - 3.2. CITY OF SAUSALITO ROAD CLOSURE/TRAFFIC DELAY PERMIT
 - 3.3. CALTRANS ENCROACHMENT PERMIT
4. CONTRACTOR SHALL MEET WITH CITY PRIOR TO START OF CONSTRUCTION. 48 HOURS NOTICE IS REQUIRED ON ALL INSPECTIONS.
5. DUST CONTROL DURING ALL PHASES OF CONSTRUCTION IS THE RESPONSIBILITY OF THE CONTRACTOR. ADJOINING STREETS AND PRIVATE DRIVEWAYS SHALL BE KEPT CLEAN OF PROJECT DIRT, MUD, MATERIALS AND DEBRIS, TO THE SATISFACTION OF THE ENGINEER.
6. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL SUBMIT FOR APPROVAL THE PROPOSED ROUTES FOR ALL CONSTRUCTION TRAFFIC RELATED TO THE PROJECT. UPON APPROVAL, THE CONTRACTOR SHALL STRICTLY ADHERE TO THE ROUTES ONLY. IN ADDITION TO THE CONTRACTOR'S PROPOSED ROUTE'S, A DETOUR PLAN SHALL BE SUBMITTED FOR APPROVAL BY THE CITY.
7. CONTRACTOR SHALL MAINTAIN ACCESS TO RESIDENCES AND BUSINESSES AFFECTED BY THE PROJECT THROUGHOUT THE DURATION OF THE CONTRACT ACCORDING TO THE SPECIFICATIONS. THE CONTRACTOR SHALL AT NO TIME BLOCK ACCESS TO RESIDENTS WITHOUT THE ADVANCE APPROVAL OF THE ENGINEER AND NOTIFICATION OF THE RESIDENT.
8. THE CONTRACTOR SHALL BE REQUIRED TO KEEP ALL CONSTRUCTION ACTIVITIES WITHIN THE RIGHTS-OF-WAY AND EASEMENTS OBTAINED FOR THIS PROJECT UNLESS OTHERWISE SHOWN. THIS SHALL INCLUDE, BUT NOT BE LIMITED TO, VEHICLES AND EQUIPMENT, LIMITS OF TRENCH EXCAVATIONS, AND STOCKPILED NEW MATERIAL.
9. CONTRACTOR SHALL NOTIFY THE UNDERGROUND SERVICES ALERT (U.S.A) 811 TWO WORKING DAYS PRIOR TO THE START OF ANY EXCAVATION OR DEMOLITION OF IMPROVEMENTS.
10. CONTRACTOR SHALL EXERCISE DUE CAUTION DURING CONSTRUCTION TO PROTECT ANY EXISTING LANDSCAPING, FIXTURES, EQUIPMENT, CONCRETE SIDEWALK, CONCRETE CURB AND GUTTER, AND AC PAVING TO REMAIN. ANY DAMAGE RESULTING FROM CONTRACTOR OPERATIONS SHALL BE REPAIRED AS DIRECTED BY THE ENGINEER, AT NO ADDITIONAL COST TO THE CITY.
11. TRAFFIC CONTROL DURING CONSTRUCTION SHALL BE THE CONTRACTOR'S RESPONSIBILITY AND IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGMEN, AND OTHER DEVICES NECESSARY TO ENSURE PUBLIC SAFETY WITHIN THE PROJECT SITE.
12. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL PERFORM A SITE WALK OF EACH STREET TO IDENTIFY ANY SURVEY MONUMENTS WITHIN THE PROJECT LIMITS. THE CONTRACTOR SHALL HIRE A LICENSED LAND SURVEYOR TO FILE A CORNER RECORD FOR THE CITY OF SAUSALITO MONUMENT IN ACCORDANCE WITH SECTION 8771 OF THE PROFESSIONAL LAND SURVEYORS ACT.
13. LOCATIONS OF LOCAL AC REPAIRS SHOWN ON THE PLANS ARE APPROXIMATE. ACTUAL LOCATIONS TO BE DETERMINED BY THE ENGINEER PRIOR TO CONSTRUCTION.
14. CONTRACTOR SHALL RESTORE ALL EXISTING PRIVATE AND PUBLIC IMPROVEMENTS DAMAGED BY THEIR OPERATIONS TO THEIR EXISTING CONDITION OR BETTER. THIS INCLUDES, BUT IS NOT LIMITED TO ALL LANDSCAPING, IRRIGATION, DRIVEWAYS, AC PAVING, CONCRETE WORK AND UTILITIES UNLESS NOTED OR DIRECTED OTHERWISE BY THE CITY'S REPRESENTATIVE.

SURFACE RESTORATION NOTES:

1. ALL PAVEMENT CUTS SHALL BE SAWCUT, SMOOTH AND VERTICAL. THE PAVEMENT AREA BEING REMOVED SHALL BE RECTANGULAR, UNLESS SHOWN OTHERWISE ON PLANS.
2. TACK COAT SHALL BE APPLIED (HORIZONTAL AND VERTICAL) PRIOR TO PLACEMENT OF NEW AC ON ALL EXISTING AC AND EXISTING PCC SURFACES.
3. CONTRACTOR SHALL RESTORE ALL EXISTING PRIVATE AND PUBLIC IMPROVEMENTS DAMAGED BY THEIR OPERATIONS TO THEIR EXISTING CONDITION OR BETTER. THIS INCLUDES, BUT IS NOT LIMITED TO ALL LANDSCAPING, IRRIGATION, DRIVEWAYS, AC PAVING, CONCRETE WORK AND UTILITIES UNLESS NOTED OR DIRECTED OTHERWISE BY THE CITY'S REPRESENTATIVE.
4. RIMS OF EXISTING UTILITY BOXES AND OTHER RELATED APPURTENANCES THAT ARE TO REMAIN SHALL BE PROTECTED DURING CONSTRUCTION AND SHALL BE ADJUSTED TO FINISH GRADES TO MAINTAIN ACCESSIBLE PATH. ANY DAMAGE RESULTING TO EXISTING UTILITY FACILITIES FROM CONTRACTOR OPERATIONS SHALL BE REPAIRED AS DIRECTED BY THE APPROPRIATE AGENCY AT NO ADDITIONAL COST TO THE CITY OR UTILITY OWNER.
5. ALL MANHOLES, VALVES AND MONUMENT FRAMES SHALL BE SET TO FINISH GRADE SUCH THAT THERE ARE NO IRREGULARITIES WITH FINISHED GRADES.
6. PROVIDE SMOOTH CONFORM TO EXISTING AC PAVEMENT AT ALL TRANSITIONS.
7. SOFT SUBGRADE REPAIRS, BASE FAILURE REPAIRS, AND ASPHALT REPAIRS ARE SHOWN IN APPROXIMATE AREAS. CONTRACTOR SHALL COORDINATE WITH ENGINEER TO FINALIZE LOCATION AND SIZE OF REPAIR AREAS. CONTRACTOR SHALL COORDINATE FINAL REPAIR AREAS AFTER MILLING OPERATIONS.
8. THE MICROSURFACE MATERIAL SHOULD NOT COVER THE EXISTING GUTTER. IF THE EXISTING LIP OF GUTTER IS VISIBLE, IT SHALL BE THE LIMIT OF MICROSURFACE. IF NO LIP OF GUTTER IS VISIBLE, CONTRACTOR SHALL CONTACT THE CITY ENGINEER TO DETERMINE THE LIMIT OF GUTTER.
9. ALL EXISTING PAVEMENT MARKINGS SHALL BE REMOVED PRIOR TO APPLICATION OF MICROSURFACE.



STRIPING NOTES

1. PAVEMENT MARKINGS TO BE FIELD VERIFIED AND APPROVED BY CITY ENGINEER. THE CONTRACTOR SHALL PROVIDE 24 HOUR NOTICE FOR FIELD VERIFICATION OF PAVEMENT MARKINGS.







ABBREVIATIONS

AC	ASPHALT CONCRETE
APRX.	APPROXIMATE
AVE	AVENUE
BLVD	BOULEVARD
C.O.M.	COUNTY OF MARIN
CA	CALIFORNIA
CB	CATCH BASIN
CO	CLEANOUT
DR	DRIVE
EX	EXISTING
FH	FIRE HYDRANT
GV	GAS VALVE
HMA	HOT MIX ASPHALT
JB	JUNCTION BOX
L	LENGTH
MAX	MAXIMUM
MIN	MINIMUM
MH	MANHOLE
N	NORTH
O.C.	ON CENTER OR OVERCROSSING
PCC	PORTLAND CEMENT CONCRETE
PL	PLACE
S	SPACING
SO.	SOUTH
SD	STORM DRAIN
SS	SANITARY SEWER
ST	STREET
TYP	TYPICAL
U.S.	UNITED STATES
W	WIDTH
WV	WATER VALVE

EXISTING UTILITIES LEGEND

CO ●	CLEANOUT
FH + ● +	FIRE HYDRANT
	STORM DRAIN CATCHBASIN
	UTILITY MANHOLE
SDJB □	STORM DRAIN JUNCTION BOX
WV ⊗	WATER VALVE

STRIPING LEGEND


STOP	'STOP' PAVEMENT MARKING WORD, SEE CALTRANS STANDARD PLAN A24D ON SHEET CD.02 DETAIL 1.
SLOW	'SLOW' PAVEMENT MARKING WORD, SEE CALTRANS STANDARD PLAN A24D ON SHEET CD.02 DETAIL 1.
AHEAD	'AHEAD' PAVEMENT MARKING WORD, SEE CALTRANS STANDARD PLAN A24D ON SHEET CD.02 DETAIL 1.
15	'15' PAVEMENT MARKING NUMBER, SEE CALTRANS STANDARD PLAN A24C ON SHEET CD.02 DETAIL 1.
	4" YELLOW CENTER LINE STRIPING, SEE CALTRANS DETAIL A20A ON SHEET CD.02 DETAIL 2.
	12" THERMOPLASTIC STOP BAR, SEE CALTRANS STANDARD PLAN A24E 'LIMIT LINE (STOP LINE)'.
	BLUE RETROREFLECTIVE RAISED PAVEMENT MARKER, SEE CA MUTCD SECTION 3B.11 'LOCATION MARKERS FOR FIRE HYDRANTS'.
	MODIFIED CONTINENTAL CROSSWALK STRIPING, SEE DETAIL 5 SHEET CD.01
	PARKING 'T' STRIPING, SEE DETAIL 4 SHEET CD.01
	PARKING 'L' STRIPING, SEE DETAIL 4 SHEET CD.01
<div>STRIPING DETAIL SEE 2015 CALTRANS STANDARD PLANS</div> <div>LENGTH IN FEET</div> <div><div>D21A20A500</div></div> <div>SHEET NUMBER SEE 2015 CALTRANS STANDARD PLANS</div>	



Know what's below.
Call before you dig.


REVISIONS						DESCRIPTION	BY	DATE	APPVD
NO.	DATE	DESCRIPTION	BY	DATE	APPVD				



 <div>711 GRAND AVENUE SUITE 240 SAN RAFAEL, CA 94901 415-930-7980 (TEL) 415-930-7979 (FAX)</div> <div>ENGINEERS / SURVEYORS / PLANNERS</div>	CHECKED	DBJ	DBJ
	DRAWN	BS	CL


2018 SAUSALITO STREETS RESURFACING PROJECT	GENERAL NOTES LEGEND AND ABBREVIATIONS MARIN COUNTY	SAUSALITO	CALIFORNIA
---	---	-----------	------------

DATE	JULY 2018	SCALE	AS SHOWN
BKF PROJECT NO.	20165272		
CLIENT	CITY OF SAUSALITO		
SHEET NO.	2	OF	15
DRAWING NO.	GN.01		




NOTES

1. FOR ASPHALT REPAIR AREAS AND LOCATIONS, REFER TO CONSTRUCTION DRAWINGS
2. IF SOFT SUBGRADE OR SUBGRADE IS EXPOSED DURING ASPHALT REPAIR OPERATIONS, THE CONTRACTOR SHALL SCARIFY AND RECOMPACT THE EX. SUBGRADE IN ACCORDANCE WITH THE SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER.



NOTES

1. FOR ASPHALT REPAIR AREAS AND LOCATIONS, REFER TO CONSTRUCTION DRAWINGS
2. IF PCC IS ENCOUNTERED DURING BASE FAILURE REPAIR OPERATIONS, THE CONTRACTOR SHALL FULLY REMOVE THE PCC PRIOR TO SCARIFICATION AND RECOMPACTION
3. IF SOFT SUBGRADE OR SUBGRADE IS EXPOSED DURING ASPHALT REPAIR OPERATIONS, SEE DETAIL 3 THIS SHEET.



REVISIONS

NO.	DESCRIPTION	BY	DATE	APPVD
1	1			
2	2			
3	3			
4	4			
5	5			
6	6			
7	7			
8	8			
9	9			
10	10			
11	11			
12	12			
13	13			
14	14			
15	15			
16	16			
17	17			
18	18			
19	19			
20	20			
21	21			
22	22			
23	23			
24	24			
25	25			
26	26			
27	27			
28	28			
29	29			
30	30			
31	31			
32	32			
33	33			
34	34			
35	35			
36	36			
37	37			
38	38			
39	39			
40	40			
41	41			
42	42			
43	43			
44	44			
45	45			
46	46			
47	47			
48	48			
49	49			
50	50			
51	51			
52	52			
53	53			
54	54			
55	55			
56	56			
57	57			
58	58			
59	59			
60	60			
61	61			
62	62			
63	63			
64	64			
65	65			
66	66			
67	67			
68	68			
69	69			
70	70			
71	71			
72	72			
73	73			
74	74			
75	75			
76	76			
77	77			
78	78			
79	79			
80	80			
81	81			
82	82			
83	83			
84	84			
85	85			
86	86			
87	87			
88	88			
89	89			
90	90			
91	91			
92	92			
93	93			
94	94			
95	95			
96	96			
97	97			
98	98			
99	99			
100	100			



BKF
711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415-930-7960 (TEL)
415-930-7979 (FAX)

ENGINEERS / SURVEYORS / PLANNERS

CALIFORNIA


MARIN COUNTY

SAUSALITO

2018 SAUSALITO STREETS
RESURFACING PROJECT


CONSTRUCTION DETAILS

DATE JULY 2018	SCALE AS SHOWN
BKF PROJECT NO. 20165272	
CLIENT CITY OF SAUSALITO	
SHEET NO. 3 OF 15	
DRAWING NO. CD.01	



NOTES

1. ALL PARKING TEES SHALL BE WHITE THERMOPLASTIC AND CONTAIN REFLECTIVE COMPONENT.
2. LOCATIONS AND SPACE OF PARKING TEES SHALL MATCH EXISTING. ALL LOCATIONS OF EXISTING PARKING TEES SHALL BE MARKED ON CURB PRIOR TO CONSTRUCTION UNLESS DIRECTED OTHERWISE.




NOTES

1. STRIPING SHALL NOT INTERFERE WITH BIKE LANES. WHERE PRESENT, STRIPE OUTSIDE BIKE LANE.
2. STRIPES SHALL BE 24" IN WIDTH AND ORIENTED PARALLEL TO THE DIRECTION OF TRAFFIC FLOW.
3. FOR ALL STRIPING, CONTRACTOR SHALL USE THERMOPLASTIC PAINT WITH RETROREFLECTIVE GLASS BEADS. THERMOPLASTIC THICKNESS SHALL BE 0.07" MINIMUM.
4. WHERE PRACTICABLE, ADJUST SPACING BETWEEN STRIPES SO THAT STRIPES ARE CENTERED ON LANE LINES.
5. STRIPES SHALL BE SPACED EVENLY WITH APPROXIMATELY 48" CLEAR SPACE BETWEEN PAINTED AREAS. SPACING BETWEEN STRIPES SHALL NOT EXCEED 60".
6. STRIPING TO BE CENTERED ON CENTERLINE, OR MEDIAN FOR DIVIDED ROADWAYS.
7. PRIOR TO STRIPING, CONTRACTOR SHALL LAYOUT CROSSWALK AND RECEIVE APPROVAL FROM CITY.
8. EXISTING STRIPING SHALL BE REMOVED BY GRINDING AND DISPOSED OF IN ACCORDANCE WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS.
9. STRIPES TO BE 10 FEET LONG. WHERE MEDIAN ENCLOSES INTO CROSSWALK, A MINIMUM OF 6 FEET LONG IS ACCEPTABLE, IF APPROVED BY ENGINEER.




1

CALTRANS PAVEMENT MARKING DETAILS
NOT TO SCALE




19



2

CALTRANS STRIPING DETAILS
NOT TO SCALE



REVISIONS

NO.	DESCRIPTION	BY	DATE	APPROVED
1				
2				
3				
4				



711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415-930-7980 (TEL)
415-930-7979 (FAX)


BKF
ENGINEERS / PLANNERS
SURVEYORS

DESIGNED:	CL
CHECKED:	DBJ
APPROVED:	DBJ

2018 SAUSALITO STREETS
RESURFACING PROJECT

CONSTRUCTION DETAILS
MARIN COUNTY

DATE	JULY 2018	SCALE	AS SHOWN
BKF PROJECT NO.	20165272		
CLIENT	CITY OF SAUSALITO		
SHEET NO.	4 OF 15		
DRAWING NO.	CD.02		



PLAN VIEW
SCALE: 1" = 20'



PHOTO 1
LOOKING SOUTHWEST

LEGEND


- APPROXIMATE RIGHT OF WAY LINE
- ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01



MICROSURFACE, SEE SPECIFICATIONS
AREA: 54,000 SF

NOTES

- BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER
- SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
- EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
- MICROSURFACE LIMITS SHALL EXTEND FROM PAVEMENT EDGE TO PAVEMENT EDGE
- STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
- LOCATIONS OF PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING. EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO DEMOLITION.



REVISIONS		NO.	DESCRIPTION	BY	DATE	APPVD

REGISTERED PROFESSIONAL ENGINEER
DAVID S. JOHNSON
No. C 061408
CIVIL
STATE OF CALIFORNIA

711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415-990-7990 (TEL)
415-990-7979 (FAX)

ENGINEERS / PLANNERS

SURVEYORS

BKFSURVEYORS

ENGINEERS / PLANNERS


DRAWN	BS	CHECKED	DBJ
DESIGNED	CL	APPROVED	DBJ

2018 SAUSALITO STREETS
RESURFACING PROJECT

IMPROVEMENT PLAN - SPENCER AVE

SAUSALITO MARIN COUNTY CALIFORNIA

DATE	JULY 2018	SCALE	AS SHOWN
BKF PROJECT NO.	20165272		
CLIENT	CITY OF SAUSALITO		
SHEET NO.	5	OF	15
DRAWING NO.	IM.01		



PLAN VIEW
SCALE: 1" = 20'

LEGEND


- — — — — APPROXIMATE RIGHT OF WAY LINE
- - - - - ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01



MICROSURFACE, SEE SPECIFICATIONS
AREA: 54,000 SF

NOTES

1. BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER.
2. SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
3. EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
4. MICROSURFACE LIMITS SHALL EXTEND FROM PAVEMENT EDGE TO PAVEMENT EDGE.
5. STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
6. LOCATIONS OF PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING. EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO DEMOLITION.



SCALE: 1" = 20'

REVISIONS				
NO.	DESCRIPTION	BY	DATE	APPROVED
1				
2				
3				
4				
5				



BKF
711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415-930-7960 (TEL)
415-930-7979 (FAX)


DRAWN:	BS	CHECKED:	DBJ
DESIGNED:	CL	APPROVED:	DBJ

2018 SAUSALITO STREETS
RESURFACING PROJECT

IMPROVEMENT PLAN - SPENCER AVE

SAUSALITO MARIN COUNTY CALIFORNIA

DATE	SCALE
JULY 2018	AS SHOWN
SHEET NO.	
20165272	
CLIENT	
CITY OF SAUSALITO	
SHEET NO.	
6 OF 15	
DRAWING NO.	
IM.02	



REVISIONS				
△				
△				
△				
△				
△				
NO.	DESCRIPTION	BY	DATE	APPVD



 BKF 711 GRAND AVENUE SUITE 240 SAN RAFAEL, CA 94801 (415) 930-3970 (TEL) (415) 930-3970 (FAX)	ENGINEERS / SURVEYORS / PLANNERS		CHECKED:
	BS	CL	DBJ
DESIGNED:			APPROVED:

2018 SAUSALITO STREETS RESURFACING PROJECT	IMPROVEMENT PLAN - CALEDONIA ST	SAUSALITO	MARIN COUNTY	CALIFORNIA
---	---------------------------------	-----------	--------------	------------

DATE	SCALE
JULY 2018	AS SHOWN
BKF PROJECT NO.	
20165272	
CLIENT	
CITY OF SAUSALITO	
SHEET NO.	
9	OF 15
DRAWING NO.	
IM.05	

PLAN VIEW

SCALE: 1" = 20'



PHOTO 1
LOOKING NORTHEAST



PHOTO 2
LOOKING NORTHWEST

LEGEND

 APPROXIMATE RIGHT OF WAY LINE


 ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01




MICROSURFACE, SEE SPECIFICATIONS
TOTAL AREA: 72,000 SF

NOTES

1. BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER
2. SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
3. EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
4. MICROSURFACE LIMITS SHALL EXTEND FROM GUTTER PAN TO GUTTER PAN
5. STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
6. LOCATIONS OF PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING. EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO OBLITERATION
7. LOCATIONS AND SPACE OF PARKING TEES SHALL MATCH EXISTING. ALL LOCATIONS OF EXISTING PARKING TEES SHALL BE MARKED ON CURB PRIOR TO CONSTRUCTION.



SCALE: 1" = 20'



SCALE: 1" = 20'

- LEGEND**
- — — — — APPROXIMATE RIGHT OF WAY LINE
- — — — — ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01

 MICROSURFACE, SEE SPECIFICATIONS
TOTAL AREA: 72,000 SF

NOTES


1. BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER
2. SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
3. EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
4. MICROSURFACE LIMITS SHALL EXTEND FROM GUTTER PAN TO GUTTER PAN
5. STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
6. LOCATIONS OF EXISTING PAVEMENT MARKINGS SHALL MATCH EXISTING EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO OBLITERATION.
7. LOCATIONS AND SPACE OF PARKING TEES SHALL MATCH EXISTING. ALL LOCATIONS OF EXISTING PARKING TEES SHALL BE MARKED ON CURB PRIOR TO CONSTRUCTION.




PHOTO 1
LOOKING SOUTHEAST



PHOTO 2
LOOKING NORTHWEST

[illegible]



PLAN VIEW
SCALE: 1" = 20'

LEGEND

- APPROXIMATE RIGHT OF WAY LINE
- ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01
- MICROSURFACE, SEE SPECIFICATIONS
TOTAL AREA: 72,000 SF

NOTES



- BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER
- SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
- EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
- MICROSURFACE LIMITS SHALL EXTEND FROM GUTTER PAN TO GUTTER PAN
- STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
- LOCATIONS OF PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING. EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO OBLITERATION.
- LOCATIONS AND SPACE OF PARKING TEES SHALL MATCH EXISTING. ALL LOCATIONS OF EXISTING PARKING TEES SHALL BE MARKED ON CURB PRIOR TO CONSTRUCTION.



PHOTO 1
LOOKING SOUTHEAST



PHOTO 2
LOOKING NORTHWEST



REVISIONS		NO.	DESCRIPTION	BY	DATE	APP'D

REGISTERED PROFESSIONAL ENGINEER
DANE S. JOHNSON
No. C 061408
CIVIL
STATE OF CALIFORNIA

711 GRAND AVENUE
SUITE 240
SAN RAFAEL, CA 94901
415-990-7960 (TEL)
415-990-7979 (FAX)

BKF
ENGINEERS / SURVEYORS / PLANNERS


BROWN	BS	CHECKED	DBJ
DESIGNED	CL	APPROVED	DBJ

2018 SAUSALITO STREETS
RESURFACING PROJECT

IMPROVEMENT PLAN - CALEDONIA ST

Sausalito Marin County CALIFORNIA

DATE	JULY 2018	SCALE	AS SHOWN
BKF PROJECT NO.	20165272		
CLIENT	CITY OF SAUSALITO		
SHEET NO.	11 OF 15		
DRAWING NO.	IM.07		



PLAN VIEW
SCALE: 1" = 20'

LEGEND


- APPROXIMATE RIGHT OF WAY LINE
- ASPHALT REPAIR, SEE DETAILS 1, 2, AND 3 SHEET CD.01
- MICROSURFACE, SEE SPECIFICATIONS
TOTAL AREA: 72,000 SF

NOTES

- BASE REPAIR LOCATIONS SHALL BE VERIFIED IN FIELD PRIOR TO CONSTRUCTION BY CITY ENGINEER
- SEE GN.01 FOR ABBREVIATIONS AND LEGENDS
- EXISTING UTILITY STRUCTURES ARE FOR REFERENCE ONLY
- MICROSURFACE LIMITS SHALL EXTEND FROM GUTTER PAN TO GUTTER PAN
- STATION LINE IS APPROXIMATE AND FOR REFERENCE ONLY
- LOCATIONS OF PROPOSED PAVEMENT MARKINGS SHALL MATCH EXISTING. EXISTING PAVEMENT MARKINGS SHALL BE LOCATED AND REFERENCED IN FIELD PRIOR TO OBLITERATION.
- LOCATIONS AND SPACE OF PARKING TEES SHALL MATCH EXISTING. ALL LOCATIONS OF EXISTING PARKING TEES SHALL BE MARKED ON CURB PRIOR TO CONSTRUCTION.



PHOTO 1
LOOKING SOUTHWEST



REVISIONS				
NO.	DESCRIPTION	BY	DATE	APP'D




711 GRAND AVENUE SUITE 240 SAN RAFAEL, CA 94901 415-990-7990 (TEL) 415-990-7979 (FAX) BKF ENGINEERS / SURVEYORS / PLANNERS	CHECKED	DBJ
	APPROVED	DBJ
	DRAWN	BS
	DESIGNED	CL

2018 SAUSALITO STREETS
RESURFACING PROJECT
IMPROVEMENT PLAN - CALEDONIA ST
SAUSALITO MARIN COUNTY CALIFORNIA

DATE JULY 2018	SCALE AS SHOWN
BKF PROJECT NO. 20165272	
CLIENT CITY OF SAUSALITO	
SHEET NO. 12 OF 15	
DRAWING NO. IM.08	

K:\2016\165272_Sausalito 2016-2019 Street Rehab\ENG\SHEETS\2018 Sausalito Streets\Phase 1\03-04_SSIMP.dwg 7-26-18 07:13:05 AM lind
PLOT SCALE: 1" = 1' VIEWPORT ROTATION: XX'




PLAN VIEW
SCALE: 1" = 20'

LEGEND

--- APPROXIMATE RIGHT OF WAY LINE

NOTES

- SEE GN.01 FOR ABBREVIATIONS AND LEGENDS



2018 SAUSALITO STREETS RESURFACING PROJECT		DATE JULY 2018		SCALE AS SHOWN	
IMPROVEMENT PLAN - WOLFBACK RIDGE ROAD		BKF PROJECT NO. 20165272		CLIENT CITY OF SAUSALITO	
SAUSALITO		SHEET NO. 13 OF 15		DRAWING NO. IMP.09	
MARIN COUNTY		DESIGNED: CL		CHECKED: DBJ	
CALIFORNIA		APPROVED: DBJ		DESIGNED: DBJ	
ENGINEERS / SURVEYORS / PLANNERS		REGISTERED PROFESSIONAL ENGINEER DAVID B. JOHNSON No. C 061408 CIVIL STATE OF CALIFORNIA		REVISIONS	
711 GRAND AVENUE SUITE 200 SAN RAFAEL, CA 94801 415-830-7860 (TEL) 415-830-7879 (FAX)		NO.		DESCRIPTION	
		BY		DATE	
		APPROVED		APPROVED	

K:\2016\165272_Sausalito 2016-2019 Street Rehab\ENG SHEETS\2018 Sausalito Streets\Phase 1\05_SSTOP.dwg 7-25-18 10:05:37 AM lind
PLOT SCALE: 1" = 1' VIEWPORT ROTATION: XX




- LEGEND:
- PROJECT LIMITS
 - DIRECTION OF TRAVEL
 - FLAGGER
 - TEMPORARY BARRIER, SEE PLAN FOR TYPE
 - TEMPORARY CONSTRUCTION SIGN, SEE SIGN CODE CHART FOR DETAILS

SIGN AND STRIPE CODE CHART		
W20-3	3 EA	ROAD CLOSED AHEAD

- NOTES:
- REFER TO CALTRANS STANDARDS FOR FURTHER TRAFFIC CONTROL DETAILS AND NOTES SHEET DT-01
 - ADDITIONAL DETOUR SIGN SHALL BE PLACED AT THE NEXT EXIT
 - ALL TRAFFIC CONTROL SHALL MEET 2015 CALTRANS STANDARD PLANS

TRAFFIC CONTROL PLAN
NO SCALE



DATE		SCALE	
JULY 2018		AS SHOWN	
BKFP PROJECT NO.			
20165272			
CLIENT			
CITY OF SAUSALITO			
SHEET NO.			
14 OF 15			
DRAWING NO.			
TC.01			

SAUSALITO		MARIN COUNTY		CALIFORNIA	
-----------	--	--------------	--	------------	--

2018 SAUSALITO STREETS RESURFACING PROJECT	
TRAFFIC CONTROL PLAN	

BKF	
711 GRAND AVENUE SUITE 240 SAN RAFAEL, CA 94901 415-395-7590 (TEL) 415-395-7579 (FAX)	
ENGINEERS / SURVEYORS / PLANNERS	
BROWN	BS
DESIGNED:	CL
CHECKED:	DBJ
APPROVED:	DBJ

REGISTERED PROFESSIONAL ENGINEER	
DAVE B. JOHNSON	
No. C 061408	
CIVIL	
STATE OF CALIFORNIA	

REVISIONS	
NO.	DESCRIPTION
BY	DATE
APP'D	

